

To: 6 030920  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-3-87  
API NUMBER 15- 193-20,183-00-00

TECHNICIAN'S PLUGGING REPORT

C NW NE , SEC. 13 , T 6 S, R 32 W/E  
4620 feet from S section line  
1980 feet from E section line

Operator License # None

Operator: Don Ziegelmeier  
Name & Address: R.R. 2 Box 18  
Rexford, Ks. 67753

Lease Name Ziegelmeier Well # 3  
County Thomas 40.63  
Well Total Depth 1250 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet NA

\* Originally: Energy Oil Inc. 4/27/79

Abandoned Oil Well Gas Well  Input Well SWD Well D&A

Other well as hereinafter indicated Pursuant to 55-179 Docket # ( 154,867-C  
C-22,446 )

Plugging Contractor Allied Cmt. Co. License Number  
Address Plainville, Ks.

Company to plug at: Hour: AM Day: 3 Month: 8 Year: 19 87

Plugging proposal received from Don Ziegelmeier ( Assisted by Carl Goodrow, KCC )  
(company name) Landowner (phone)

were: 8 5/8 w/500 sx 4 1/2" csg. set at 1250' circulated cement to surface  
order 100 sx. A.T.L. cement blend 65/35 poz 10% gel 2% dical 5 sx hulls.  
Allied Cmt. Co. Newman Water Truck

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 9:15 AM Day: 3 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT Squeeze down 4 1/2 with 400 # hulls mixed in with 25 sx. cmt. blend  
Max. 1200 # locked up  
Close in 400# plug complete.

Tie on to backside would not take cmt. Cement circulated to surface on backside.  
Tested backside to 1500 # P.S.I.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-6-87

Signed Carl Goodrow (TECHNICIAN) D

INV. NO. 17739