

6 030919

8-3-87

API NUMBER 15- 193-20,175 -00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NE SW, SEC. 12, T 6 S, R 32 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # None

Operator: Don Ziegelmeier

Name & Address R.R. 2 Box 18

Rexford, Kansas 67553

1980 feet from S section line

3300 feet from E section line

Lease Name Ziegelmeier Well # 2

County Thomas 157.61

Well Total Depth 4665 feet

Conductor Pipe: Size \_\_\_\_\_ feet

\*Originally: Energy Oil Inc. 9/20/78

Surface Casing: Size 8 5/8 feet 368 100

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well 154,867-C D&A \_\_\_\_\_

Other well as hereinafter indicated Pursuant to 55-179 Docket # ( 5-22,446 )

Plugging Contractor Allied Cmt. Co. License Number \_\_\_\_\_

Address Plainville, Ks.

Company to plug at: Hour: AM Day: 3 Month: 8 Year: 19 87

Plugging proposal received from Don Ziegelmeier ( Assisted by Carl Goodrow, KCC)

(company name) \_\_\_\_\_ Landowner \_\_\_\_\_ (phone) \_\_\_\_\_

were: 8 5/8 at 368' w/ 100 sx. 4 1/2" at 4250' w/100 sx Perf. 4475-4478 4 1/2" csg

was pulled earlier. Order 200 sx cmt. blend ATL 65/35 poz 10% gel 2% dicel 5 sx hulls

Allied Cmt. Co. Newman Water Truck

Plugging Proposal Received by Carl Goodrow Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11: AM Day: 3 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT Bottom was plugged and pipe pulled but no record is available

Ran wireline to 2600' tagged bottom, hole tight with bridges but open.

Squeeze down 8 5/8 w/500 # hulls in with 125 sx cmt. blend A.T.L. Max. P.S.I. 700#/close

in 300 # Plug complete.

8-6-87

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 8-6-87

INV. NO. 17738

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow