

6 030918

8-3-87

API NUMBER 19- 193-20,171-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SE SW, SEC. 12, T 6 S, R 32 W/E

330 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # None

Lease Name Ziegelmeier Well # 1

Operator: Don Ziegelmeier

County Thomas 151.13

Name & Address R.R. 2 18

Well Total Depth 4650 feet

Rexford, Kansas 67753

Conductor Pipe: Size \_\_\_\_\_ feet

\* Originally: Energy Oil Inc. 9/7/78

Surface Casing: Size 8 5/8 feet 712'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated Pursuant to 55-179 Docket # 154,867-C  
(c-22,446)

Plugging Contractor Allied Cmt. Co. License Number \_\_\_\_\_

Address Plainville, Ks.

Company to plug at: Hour: \_\_\_\_\_ PM Day: 3 Month: 8 Year: 19 87

Plugging proposal received from Don Ziegelmeier ( Assisted by Carl Goodrow, KCC)

(company name) \_\_\_\_\_ Landowner \_\_\_\_\_ (phone) \_\_\_\_\_

were: 8 5/8 set at 712 w/200 sx. 4 1/2 set at 4600 with 100 sx Perf. 4414-17' 4 1/4 csg was  
pulled earlier ran wireline to 2600' hole tight but open ordered 200 sx ATL

65/35 poz 10% gel 2% dicel 6 sx hulls. Allied Cmt. Co.

Joe Newman Water Truck

Plugging Proposal Received by Carl Goodrow Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 PM Day: 3 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT Bottom was plugged and pipe was pulled but no record is  
available. Ran wireline to 2600' tagged bottom, hole tight with bridges but open

Squeezed 8 5/8 w/600 # hulls mixed in with 125 sx ATL Cmt. Blend. Max. PSI 500 #  
close in PSI 300 # Plug complete

8-6-87  
APR 6 1987

Remarks: Dakota Top 1600' Anhy 2680'

(If additional description is necessary, use BACK of this form.)

**INVOICED**

Reserve this plugging.

DATE 8-6-87

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow

INV. NO. 17737