

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-00209-00-00
Spot: NENESW Sec/Twnshp/Rge: 11-30S-36W
2507 feet from S Section Line, 2886 feet from E Section Line
Lease Name: KOENIG Well #: 2-11
County: GRANT Total Vertical Depth: 2730 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
L1		2723		SLOTTED LINER
PROD	7	2525	✓ 1027	WITH 125 SX CMT
SURF	10.75	579		WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/01/2005 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLS WITH 40 SX CMT. TAG TOC & TOF. PUMP MUD SPACER 1700' & PUMP 20 SX CMT. PUMP 75 SX CMT AT 600'. PUMP 20 SX CMT FROM 40' TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/03/2005 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 500# HULLS WITH 40 SX CMT. TAG TOC @ 2035'. TAG TOF @ 1900'. 1ST PLUG PUMP 8 BBL MUD SPACER TO 1700' & PUMP 20 SX CMT. 2ND PLUG PULL OUT OF HOLE TO 600'. CIRCULATE HOLE WITH MUD & PUMP 75 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE WITH MUD & PUMP 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2470	2684		


INVOICED

DATE 8-24-05
INV. NO 2006060381

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

RECEIVED

AUG 24 2005

KCC WICHITA

Form CP-238