

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-121-19708-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 24-15S-21E
815 feet from S Section Line, 4650 feet from E Section Line
Lease Name: WARREN Well #: WAR 01
County: MIAMI Total Vertical Depth: 475 feet

Operator License No.: 102
Op Name: KDOT Dist 4 Area 2
Address: 507 N. Maple
Carnett, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	475		
SURF	8	20		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/20/2005 8:00 AM
Plug Co. License No.: 3097 Plug Co. Name: K W OIL WELL SERVICE, INC.
Proposal Rcvd. from: JIM KEPLEY Company: K W OIL WELL SERVICE, INC. Phone: (620) 431-2285

Proposed Plugging Method: FILL WELL FROM TD TO SURFACE WITH PORTLAND CEMENT.

Plugging Proposal Received By: FRANK GUILFOYLE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/21/2005 5:00 PM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

Perfs:

RAN 1" INSIDE 2" TO 475', WASHED OUTSIDE OF 2" TO 350', PUMPED PORTLAND CEMENT TO SURFACE INSIDE 2" AND OUTSIDE 2". PULLED PIPE AND TOPPED OFF WELL. PUMPED TOTAL OF 145 SACKS OF CEMENT. EMPTIED PIT. DUG OUT WELL AND CUT OFF BELOW GROUND. FILLED IN PIT AND LEVELED AROUND WELL SITE.

RECEIVED
KCC DISTRICT #3
AUG 22 2005 *SK*
CHANUTE, KS

Remarks: OLD HOME USE GAS WELL

Plugged through:

District: 03

Signed Frank Guilfoyle by SK
(TECHNICIAN)

RECEIVED
AUG 24 2005
KCC WICHITA