

6 030930

AUG 24 1987

API NUMBER 15-

179-20,905-0000

283

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW \_\_\_\_\_, SEC. 27, T 6 S, R 29 W  
4980 feet from S section line  
4980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 08847

Lease Name Wessel Well # 1

Operator: Hoff Oil and Gas

County Sheridan 134.55

Name & Address Box 97

Well Total Depth 4140 feet

Lance Creek, Wy 82222

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 345/260

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling License Number 5302

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 24 Month: August Year: 19 87

Plugging proposal received from Wayne Sander

(company name) Red Tiger (phone) \_\_\_\_\_

were: Order 190 lbs. 60/40 Pozmix 6% Gel, 1 sk Hulls and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Halliburton 60/40 Pozmix 6% Gel.

Plugging Proposal Received by Carl Goodrow *Carl Goodrow*  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 4:30 PM Day: 24 Month: August Year: 19 87

ACTUAL PLUGGING REPORT

1st plug at 2550' w/25 sks

2nd plug at 1670' w/100 sks and 1 sk Hulls

3rd plug at 390' w/40 sks.

4th plug at 40' w/10 sks W. P.

15 sks in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 8 1987

CONSERVATION DIVISION  
Wichita, Kansas

9-8-87

Remarks: Anhy 2543' - 75' Elev 2816 K. B.

(If additional description is necessary, use BACK of this form.)

(did, ~~not~~) observe this plugging.

INVOICED

Signed Carl Goodrow *Carl Goodrow*  
(TECHNICIAN)

Carl Goodrow

FORM CP-2/3  
Rev. 01-84 LR

DATE 9-15-87

INV. NO. 18113

8-24

120 days.

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 8 20 87 month day year

API Number 15-179-20905-00-00

OPERATOR: License # 08847 Elmer Hoff (Hoff Oil & Gas) Name Box 97 Address Lance Creek, Wyo. 82222 City/State/Zip Elmer Hoff Contact Person 913-386-4429 Phone

NW/4 Sec. 27 Twp. 6 S, Rg. 29 East X West 4980 Ft. from South Line of Section 4980 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5302 Red Tiger Drilling Co. Name 1720 Kansas State Bk Bldg. City/State Wichita, Kansas

Nearest lease or unit boundary line 300 330 feet County Sheridan

Well Drilled For: X Oil Storage X Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Lease Name Wessel Well # 1 Ground surface elevation 2811 feet MSL

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

I certify that well will comply with K.S.A. 55-101, et seq., plugging hole to KC... Date 8-5-87 Signature of Operator or Agent

Depth to bottom of fresh water 230 Depth to bottom of usable water 1600 250

George A. Angle BY RED TIGER DRILLING CO. Title Owner

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 300 feet per Alt. 1 2

Surface pipe by Alternate: 1 2 X Surface pipe planned to be set 340

This Authorization Expires 2-6-88 Approved By Bee Agnes Aug 16-87

Conductor pipe required Projected Total Depth 4300 feet Formation Kansas City

1/2 mile E of Seldon 2 to west side

30'W of NW NW NW Sec. 27 Twp. 6 S, Rg. 29 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep. 25 sx or formation with at ANHY feet of... 60-40 poz., 6% gel 2nd plug @ ft. deep. 100 sx & 1 sk. hulls or formation with 250' from top of DAKOTA 3rd plug @ ft. deep. 40 sx or formation with 390' feet of. 4th plug @ ft. deep. 10 sx or formation with 40' feet of. 5th plug @ ft. deep or formation with feet of. (2) Rathole to surface minus 5 feet 15 sx (b) Mousehole to surface minus 5 feet

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging. In Addition: Call district office before well is either plugged or production casing is cemented in. (Call 7 a.m. to 5 p.m. workdays)

District office use only: API #15-179-20905 Surface casing of feet set with sx at hours 19 Alternate 1 or 2 surface pipe was used. Alternate 2 cementing was completed @ ft. depth with sx on 19 Hole plugged 19 agent

AUG 10 1987 RECEIVED STATE CORPORATION COMMISSION SEP 8 1987 CONSERVATION DIVISION Wichita, Kansas Form C-1 11/86