

4-031767

10-6

131

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-20,738 <sup>00-00</sup>  
80' W. of C.  
E2 SE SE /4 SEC. 16, 06 S, 29 W  
600 feet from S section line  
400 feet from E section line

Operator license# 8847

Lease Brantley well # 5

Operator: Hoff Oil & Gas Company

County Sheridan

Address: Box 49  
Selden, Kansas 67757

Well total depth 4120 feet <sup>133,90</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 388 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Halliburton License# -

Address: Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 6 Month: October Year: 92

Plugging proposal received from: Elmer Hoff

Company: Hoff Oil Company Phone: -

Were: Order 375 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Hole open to perf's.  
Pulled rods and tubing.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 10:00A.M., Day: 6, Month: October, Year: 92

Actual plugging report: 8 5/8" set @ 388' w/250 sx. cwc. 5 1/2" set  
@ 4119' w/250 sx. F.O. tool set @ 2545' w/600 sx. to surface.  
Perf. 4081' - 4086'. Squeezed 5 1/2" w/300 sx. cement blend w/500#  
hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 1000#. Test  
8 5/8" with 2 BBL. slurry to 500# backside full. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 30 1992

Remarks:     

Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO     

Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X, NO     

Plugged through TUBING     , CASING X. Elevation:      GL 10-30-92

INVOICED

I did[      ] did not[      ] observe the plugging.

Carl Goodrow

DATE NOV 03 1992

JD

(agent)

WV. NO. 36658