

KANSAS

*2*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20222-0000

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 28 1969  
CONSERVATION DIVISION  
Wichita, Kansas

7-28-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address 1515 Wichita Plaza Building, Wichita, Kansas.

Lease Name Geisinger Well No. 1

*NW NW SE*

Location 2200' FSL & 2200' FSL of Sec. 16 Twp. 6 Rge. (E) (W) 28

County Sheridan Total Depth 4180'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Red Tiger Drilling Company.

Address 1720 Wichita Plaza Building, Wichita, Kansas. License No.     

Operation Completed: Hour 5:30 PM Day 26 Month 7 Year 1969

The above well was plugged as follows:

260'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1425'.

Circulated hole with heavy mud. Pulled DP to 1640' and displaced 100 Sx. cement thru  
DP from 1640' to 1315'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from  
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 7/29/69  
INV. NO. 201-W