


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

JUN 5 1969

CONSERVATION DIVISION
Wichita, Kansas

6-5-69

15-179-20211-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address 1515 Wichita Plaza Building, Wichita, Kansas.

Lease Name Geisinger Well No. 2

Location CNW/4 Sec. 16 Twp. 6 Rge. (E) (W) 28

County Sheridan Total Depth 4172'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza Building, Wichita, Kansas. License No. _____

Operation Completed: Hour 1:30 AM Day 3 Month 6 Year 1969

The above well was plugged as follows:

310'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1400'.

Circulated hole with heavy mud. Pulled DP to 1635' and displaced 100 Sx. cement thru
DP from 1635' to 1310'. Pulled DP to 370' and displaced 20 Sx. cement thru DP from
370' to 310'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/5/69
INV. NO. 9884-u

Signed: W. L. Nichols
Well Plugging Supervisor