

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20202-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Theodore Gore,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Geisinger Well No. 1

Location NW NW NE  
440' FNL & 440' FWL of NE Sec. 16 Twp. 6 Rge. (E) (W) 28

County Sheridan Total Depth 3773'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Leben Drilling, Incorporated,

Address Box #186, Great Bend, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 9:00 PM Day 23 Month 4 Year 1969

The above well was plugged as follows:

329' -- 8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1675' and displaced 100 Sx. cement thru  
DP from 1675' to 1350'. Pulled DP to 335' and displaced 20 Sx. cement thru DP from  
335' to 275'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

APR 25 1969

4-25-69

I hereby certify that the above well was plugged as herein stated.

INVOICED

CONSERVATION DIVISION  
Wichita, Kansas

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 4/28/69

INV. NO. 9660-U