

15-779-20121-00-00

Form CP-3
Rev. 6-4-68

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION

JAN 29 1970

CONSERVATION DIVISION
Wichita, Kansas

1-29-70

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated.

Complete Address Box #922, Great Bend, Kansas.

Lease Name Geisinger Well No. 1

Location SE-SE-NW, Sec. 16 Twp. 6 Rge. (E) (W) 28

County Sheridan Total Depth 4210'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:00 PM Day 22 Month 1 Year 1970

The above well was plugged as follows:

338'--8 5/8" Surface casing, cement circulated with 250 Sx.
4210'--4 1/2" Production casing cemented on bottom with 250 Sx. Well plugged back to
4169'. Well perforated 4015' to 4019' and squeezed with 150 Sx. cement Top perfor-
ations open from 4099' to 4103'.

Sanded well back to 4000' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing
and squeezed well initially with 5 sacks hulls and 5 sacks gel and followed with 100
Sx. cement from 1650' to 1325' then 24 sacks gel from 1325' to 350' and followed with
25 Sx. cement from 350' to 275' then 6 sacks gel from 275' to 35' and finally 10 Sx.
cement from 35' to bottom of cellar. Maximum pump-in pressure-400#. Final shut-in
pressure-250#. (Mudding and cementing operations performed by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 1/29/70
INV. NO. 1311-W