

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED
FEB 19 1968

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address P. O. Box #797, Great Bend, Kansas.

Lease Name Galloup Well No. 1

Location SW-NE Sec. 31 Twp. 7 Rge. (E) (W) 24

County Graham Total Depth 3945'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 8:30 PM Day 14 Month 2 Year 1968

The above well was plugged as follows:

212'--85/8" Surface pipe, cement circulated with 170 Sx.
Dakota section from 1000' to 1175'.

Circulated hole with heavy mud. Pulled DP to 1210' and displaced 100 Sx. cement thru
DP from 1210' to 890'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 2/19/68
INV. NO. 7289-W