

KANSAS

19

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1970 *AUG 7 1970*
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name C-G Drilling Company,

Complete Address 1107 Union National Bank Building, Wichita, Kansas.

Lease Name Charles Well No. 1

Location NE-SW-SW Sec. 34 Twp. 7 Rge. (E) (W) 24

County Graham Total Depth 3810'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 5:00 AM Day 3 Month 8 Year 1970

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 100 Sx. cement thru
DP from 1125' to 800'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 8/7/70
INV. NO. 2343-W

Signed: *M. L. Nichols*
Well Plugging Supervisor