

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-179-08236-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 125-31

LOCATION SW SW NW

SEC. 27 TWP. 6 RGE. 29 W

Dry Hole Abandoned Oil Well x Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 5 Lease Wessel

Operator Westpan Hydrocarbon Address Box 30 Larned, Kans

Field County Sheridan

Total Depth 4150 Feet.

Plugging Contractor E & L Pipe Pulling

Plugging Contractor's License No. 249

Address

(Describe briefly the manner in which the well was plugged)

8 5/8" at 253' circulated with cement - 5 1/2" at 4148' with 160 sax
cement behind 1/2 perforated at ~~4040x~~ 4084'.

Filled with sand to 4070', set 4 sax cement with dump bailer,
pulled 3000' 5 1/2" - heavy mud to 240', set rock and 20 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
PLUGGING
FILE SEC 27 T 6 R 29 W
BOOK PAGE 125 LINE 31
CONSERVATION DIVISION
Wichita, Kansas
1-2-57

Edna Kelly
District Conservation Agent

Date 12-30-56