

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1969
CONSERVATION DIVISION
Wichita, Kansas

15-179-20224-0000

8-5-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Norman D. Fitzgerald,

Complete Address Box #5046, Abilene, Texas.

Lease Name Gilchrist Well No. 1

Location CSE-SW Sec. 30 Twp. 6 Rge. (E) (W)30

County Sheridan Total Depth 4500

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza Building Wichita, Kansas. License No.

Operation Completed: Hour 3:00 AM Day 4 Month 8 Year 1969

The above well was plugged as follows:

295'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1425'.

Circulated hole with heavy mud. Pulled DP to 1650' and displaced 100 Sx. cement thru
DP from 1650' to 1325'. Pulled DP to 300' and displaced 25 Sx. cement thru DP from
300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. L. Nichols*
Well Plugging Supervisor

DATE

INV. NO.