

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-179-30002-00-00

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1965
7-19-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tom-Kat, Incorporated,

Complete Address: 1125 Wichita Plaza, Wichita, Kansas.

Lease Name Farber Well No. 1

Location CSE-NE Sec. 26 Twp. 6 Rge. (E) (W) 30

County Sheridan Total Depth 4655

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 2:00PM Day 17 Month 7 Year 1965

The Above well was plugged as follows:

209'--8 5/8" Surface pipe, cement circulated with 180 Sx.

Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.

cemēnt thru DP. Heavy mud to 200', set plug with 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/19/65
INV. NO. 1490-W

Signed: A. D. Oschels
Well Plugging Supervisor