

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20258-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers,

Complete Address Shields Building, Russell, Kansas.

Lease Name ~~Duesberg~~ Deusburg Well No. 1

Location SE-SE-SW Sec. 18 Twp. 6 Rge. (E) (W) 29

County Sheridan Total Depth 4180'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 12:00 PM Day 1 Month 7 Year 1970

The above well was plugged as follows:

2941--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1500'.

Circulated hole with heavy mud. Pulled DP to, 1735' and displaced 100 Sx. cement thru
DP from 1735' to 1410'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed:

M. L. Dickels
Well Plugging Supervisor

DATE

7/6/70

JUL 6 1970

INV. NO.

2168-W

CONSERVATION DIVISION
Wichita, Kansas

7-6-70