

DISTRICT CONSERVATION AGENT'S REPORT

15-179-05586-00-00

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW NE SE

SEC. 16 TWP. 6 RGE. 29 *W*

Dry Hole Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 3 Lease Brantley

Operator Sauvage & Dunn DRILLING CO. INC. Address Oberlin, Kans

Field _____ County Sheridan

Total Depth 4115 Feet.

Plugging Contractor Sauvage & Dunn and E & L Pipe Pulling Co

Plugging Contractor's License No. 249

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement - 5 1/2" at 4115' with

150 sax cement behind - perforated at 4082 to 90 - perforations
squeezed with 368 sax cement.

Filled with sand to 4070', set 4 sax cement with dump bailer,

pulled 1880' 5 1/2" - filled hole with rotary mud to 180', set

rock and 15 sax cement, heavy mud to 35', set rock and 10 sax
cement to bottom cellar.

E. W. Petty

District Conservation Agent

Date 5-7-56

RECEIVED
STATE CORPORATION COMMISSION

MAY 9 1956

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 16 T. 6 R. 29 W.
BOOK PAGE 60 LINE 13