

JP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20157-00-00

RECEIVED
11-18-68
STATE CORPORATION COMMISSION
NOV 18 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name Ritter Well No. 1

Location SW-SW-SW Sec. 10 Twp. 6 Rge. (E) (W) 29

County Sheridan. Total Depth 4200'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No.

Operation Completed: Hour 2:30 PM Day 11 Month 11 Year 1968

The Above well was plugged as follows:

259'--8 5/8" Surface casing cement circulated with 180 Sx.
Top of Dakota section @ 1425'.

Circulated hole with heavy mud. Pulled DP to 1650' and displaced 100 Sx. cement thru
DP from 1650' to 1325'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. S. Diehls*
Well Plugging Supervisor

DATE 11/18/68

INV. NO. 8830-W