

DISTRICT CONSERVATION AGENT'S REPORT

15-179-00046-00-00

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 26-30

LOCATION SW NW NW

SEC. 27 TWP. 6 RGE. 29

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Wessell

Operator Westpan - Hydrocarbon Co Address Box 30 Larned, Kans

Field _____ County Sheridan

Total Depth 4715 Feet.

Plugging Contractor Ace Pipe Pulling

Plugging Contractor's License No. 2

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 289' circulated with cement - 5 1/2" 4145' with 180 sax
cement behind - P.B. with cement 4020' , perforated 4002'.

Filled with sand 3992', set 5 sax cement with dump bailer - pulled

1470' 5 1/2" - Hole filled with (60 sax Gel, 28 sax Hulls mixed and

pumped to 285' - set bridge and 20 sax cement - heavy chunk mud to

35' set rock and 10 sax cement to bottom cellar.

Eddon Perry

District Conservation Agent

Date 8-3-57

PLUGGED
FILE SEC 27 TWP 6 RGE 29 W
BOOK PAGE 26 LINE 30

8-6-57