

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-179-05227-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 125-31

LOCATION SW NW NW

SEC. 29 TWP. 6 RGE. 29W

Dry Hole Abandoned Oil well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. ~~A-3~~ 2 Lease _____ Neff "A"

Operator Westpan Hydro Carbon Address Box 30 Larned, Kans

Field _____ County Sheridan

Total Depth 4129 Feet.

Plugging Contractor E & L Pipe Pulling

Plugging Contractor's License No. 249

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 241' circulated with cement - 5 1/2" at 4129' with 160
sax cement behind - perforated at 4078'.

Filled with sand to 4060', set 4 sax cement with dump bailer, pulled
1200' 5 1/2" - filled hole with heavy mud to 240', set bridge and 20
sax cement, heavy mud to 35', set rock and 10 sax cement to bottom
cellar.

VED
CONSERVATION COMMISSION

FEB 1 X 1957

District Conservation Agent

Date 1-23-57

PLUGGING
FILE SEC 22 T. 6 R 29W
BOOK PAGE 125 LI E 29

CONSERVATION DIVISION
Wichita, Kansas

2-1-57