

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24353-00-00  
Spot: E2SESW Sec/Twnshp/Rge: 8-16S-13W  
660 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: BITTER C Well #: 1  
County: BARTON Total Vertical Depth: 3440 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3437	0	150 SX CMT
SURF	8.625	401	0	190 SX CMT

#111 80

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/10/2005 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: CASEY COATS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix and 500# hulls.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/10/2005 6:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with a dump bailer - sanded bottom to 3330' - topped with 5 sxs cement.  
Cut casing at 1808' - pulled to 1725'.  
Allied rigged to casing and pumped 150 sxs 60/40 pozmix with 300# hulls mixed in.  
Pulled casing to 940'. Allied rigged to casing and pumped 25 sxs cement with 50# hulls mixed in.  
Pulled casing to 360'. Allied rigged to casing and pumped 80 sxs cement with 150# hulls mixed in to circulate cement to surface.  
POOH and pulled rest of casing.  
Hole stayed full.

Perfs:


Top	Bot	Thru	Comments
3388	3389		
3292	3296		

Remarks: ALLIED CEMENTING COMPANY-TICKET #17247.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE

8-16-05

INV. NO.

200606317

RECEIVED

AUG 16 2005

KCC WICHITA

Form CP-2/3

AUG 11 2005

DEUTSCH OIL COMPANY  
WICHITA, KS 67202

8-16 -13W  
C E/2 SE SW

#1-8 BITTER "C"

site: 9-3/4 N OF HOISINGTON, KS  
contr: DUKE DRILLING COMPANY, INC  
geol: KENT DEUTSCH

city: BARTON  
field: TRAPP

API 15-009-24353


fr date 12/29/88    spd date 01/03/89    drig comp 01/09/89    card issued 03/22/89    last revised 03/22/89

ELV: 1945 KB LOG  
tops.....depth/datum  
\*ANH .....909 +1036  
\*B/ANH.....936 +1009  
TOP.....2836 -891  
HEEB.....3070 -1125  
DOUG.....3103 -1158  
LANS.....3150 -1205  
BKC.....3342 -1397  
ARB.....3388 -1443  
RTD.....3440 -1495  
\*DRILLER TOP

IP status:  
OIL, P 30 BOPD, NW, ARB 3389-3390,  
CSG: 8-5/8" 401 / 190 SX, 5-1/2" 3437 / 150 SX  
NO CORES  
DST (1) 3065-3114 (TOR), / 15-30-15-30, REC 15' OIL  
SPKD M ISIP 128# FSIP 65# IFP 50# -52# FFP 52#  
-57# IHP 1684# FHP 1643# BHT 95 °  
DST (2) 3271-3305 (KC), / 15-30-45-60, 450' GIP, REC  
90' G & OCM ISIP 119# FSIP 161# IFP 60# -62# FFP  
64# -70# IHP 1780# FHP 1751# BHT 107 °  
DST (3) 3358-3389 (ARB), / 15-30-30-60, REC 210' M &  
GCO, 300' SLI MCO ISIP 1096# FSIP 1096# IFP 65#  
-79# FFP 158# -187# IHP 1834# FHP 1807# BHT 107 °  
MICT - CO, PF (ARB) 3388.5-3389.5, W / 4 SPF, GSO,  
NAT, SET 2-7/8" TBG AT 3430, NO PKR, POP, P 30  
BOPD, NW (GR 35), 1/27/89

COPYRIGHT 1989  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS