

3 022771

15-207-19561-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019-037

SE,NE,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.

4011 feet from south section line

205 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS Fee Fund

Name & FEE FUND PLUGGING

Address

AB oil well X Gas Well SWD Well/ Input Well

Other well as hereinafter indicated:

Plugging Contractor: K-W OIL WELL SERVICE, INC.

Lic. # 3097

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: 22 Month: 7 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT MAY

HAVE BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO

PERFORATE THE 2" CASING SEVERAL TIMES AND TO CIRCULATE AS MUCH OF THE

WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part

TECHNICIAN

None X

Operations Completed: Hour: 12:00P.M. Day: 22 Month: 7 2005

Actual Plugging Report: THE 2" CASING WAS PERFORATED AT 350' AND WAS

PERFORATED AT 150'. 1" PIPE WAS RAN INTO THE 2" CASING TO 700'. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM

SURFACE. 49 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.10) (THIS WELL WAS NO.W-2 ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIANRECEIVED
AUG 02 2005
KCC WICHITA