

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10022-00-01
Spot: NESW Sec/Twnshp/Rge: 18-32S-39W
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: CRAYTON A Well #: 2
County: MORTON Total Vertical Depth: 6040 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5840		
PROD	4.5	5910	1419	WITH 475 SX CMT
SURF	8.625	1706		WITH 700 SX CMT

#196 30

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/08/2005 8:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (620) 629-4200

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT ON BOTTOM. PLUG AT 1750' WITH 15 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 07/25/2005 5:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

7/8/05: PUMPED 300# HULLS & 25 SX CMT ON BOTTOM MUD SPACER TO 1750' & PUMP 15 SX CMT. SHUT DOWN FOR VACATION. 7/25/05: PUMP 40 SX CMT AT 600'. PUMP 10 SX CM AT 40'.

Perfs:


Top	Bot	Thru	Comments
5812	5821		
5745	5750		
5726	5738		
5718	5722		
5711	5713		

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

INVOICED
DATE 8-19-05
INV. NO 2006060341

District: 01



Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
AUG 19 2005
KCC WICHITA

Form NP-23