

State of Kansas



15-179-2021-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 5 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 6-5-69

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Jerb Ogle of Red Tiger Drilling Company, has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: 1515 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Geisinger Well No. 2

Location: CNW Sec. 16 Twp. 6 Rge. (E)(W)28

County: Sheridan Total Depth 4172 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

340'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1400'.

Circulate hole with heavy mud. Pull DP to 1635' and displace 100 Sx.  
cement thru DP. Pull DP to 370' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*W. L. Nichols*

Conservation Division Agent