

State of Kansas



15479-20206-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1969

CONSERVATION DIVISION
Wichita, Kansas

5-6-69

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Theo. Gore,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name: John Geisinger Well No. 1

Location: 1320' FSL & 440' FWL ^{Su/4} Sec. 16 Twp. 6 Rge. (E)(W) 28

County: Sheridan Total Depth 4160 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

318'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1250'.

Circulate hole with heavy mud. Pull DP to 1165' and displace 100 Sx.
cement thru DP. Pull DP to 335' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent