



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Theodore Gore

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Geisinger Well No. 1

Location: 440' FNL & 440' FWL of NE Sec. 16 Twp. 6 Rge. (E)(W) 28

County: Sheridan Total Depth 3773' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

329'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1450'.

Circulate hole with heavy mud. Pull DP to 1675' and displace 100 Sx. cement thru DP. Pull DP to 335' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

RECEIVED

STATE CORPORATION COMMISSION

APR 25 1969

CONSERVATION DIVISION
 Wichita, Kansas

Very truly yours,

Conservation Division Agent