



13-179-20121-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1970
CONSERVATION DIVISION
Wichita, Kansas
1-29-70

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1970
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: Box #922, Great Bend, Kansas.

Lease Name: Geisinger Well No. 1

Location: SE-SE-NW, Sec. 16 Twp. 6 Rge. (E)(W) 28

County: Sheridan Total Depth 4210' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

338'--8 5/8" Surface casing, cement circulated with 250 Sx.
4210'--4 1/2" Production casing cemented on bottom with 250 Sx. Well
plugged back to 4169. Well perforated 4015' to 4019' and squeezed with
150 Sx. cement. Open perforations 4099' to 4103'.

Sand back to 4000' and set 3 Sx. cement with dump bailer. Pull 4 1/2"
casing and squeeze well with 5 sacks hulls, 35 sacks gel and 135 Sx.
cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent