



15-179-20224-06-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1969
CONSERVATION DIVISION
Wichita, Kansas
8-5-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerb Ogle of Red Tiger Drilling Company, has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Norman D. Fitzgerald

Complete Address: Box #5046, Abilene, Texas

Lease Name: Gilchrist Well No. 1

Location: CSE-SW Sec. 30 Twp. 6 Rge. (E)(W) 30

County: Sheridan Total Depth 4500' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

295'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1425'.

Circulate hole with heavy mud. Pull DP to 1650' and displace 100 Sx.
cement thru DP. Pull DP to 300' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent