



15-193-20031-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1970

CONSERVATION DIVISION
Wichita, Kansas

6-29-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Paul Stevens of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Stevens guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: Dean Well No. 1

Location: CNE-NE Sec. 21 Twp. 6 Rge. (E)(W) 32

County: Thomas Total Depth 4640' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stevens was instructed to plug the well as follows:

253'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1500'.

Circulate hole with heavy mud. Pull DP to 1725' and displace 100 Sx. cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent