

State of Kansas



15-179-20157-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 18 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 11-18-68

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Vernon Zorn of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Zorn guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company.

Complete Address: Victoria, Kansas.

Lease Name: Ritter Well No. 1

Location: SW-SW-SW Sec. 10 Twp. 6 Rge. (E)(W) 29

County: Sheridan Total Depth 4200' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Zorn was instructed to plug the well as follows:

259'--8 5/8" Surface, cement circulated with 180 Sx.
Top of Dakota section @ 1425'.

Circulate hole with heavy mud. Pull DP to 1650' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. S. Nichols
 Conservation Division Agent