

State of Kansas



15-193-20019-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1969
CONSERVATION DIVISION
Wichita, Kansas
5-9-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dwight Deffenbaugh of Rains & Williamson Oil Co. Inc has this date requested permission to plug the following described well:

Mr. Deffenbaugh guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Barnett Well No. A-2

Location: CSW-NE Sec. 17 Twp. 6 Rge. (E)(W) 31

County: Thomas Total Depth 4480 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Deffenbaugh was instructed to plug the well as follows:

253'--8 5/8" Surface casingm cement circulated with 160 Sx.

Circulate hole with heavy mud. Pull DP to 1850' and displace 100 Sx. cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Diehl
Conservation Division Agent