



15-193-0009-00-01

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 9 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 09-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Norman Rodie of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Rodie guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Barnett Well No. A-1

Location: NW-NW-SE Sec. 8 Twp. 6 Rge. (E)(W)31

County: Thomas Total Depth 4720 Oil Well

Gas Well Input Well AWD Well D & A X Lost Hole

Mr. Rodie was instructed to plug the well as follows:

322'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1580'.

Circulate hole with heavy mud. Pull DP to 1800' and displace 100 Sx. cement thru DP. Pull DP to 335' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
 Conservation Division Agent