

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23467-00-00
Spot: SWNENWNW Sec/Twnshp/Rge: 30-10S-17W
350 feet from N Section Line, 810 feet from W Section Line
Lease Name: JONES Well #: 1
County: ROOKS Total Vertical Depth: 3692 feet

Operator License No.: 33401
Op Name: ERNST, FRED A.
Address: 1234 WALKER AVE.
WALKER, KS 67674

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	205		

99
\$ 119

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/17/2005 4:00 PM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: DARREL ANDERSON Company: ANDERSON, C. D. DBA ANDERSON Phone: (785) 567-6144

Proposed Plugging Method: Ordered 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 07/17/2005 5:30 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Perfs:

1st. Plug at 1420' w/25 sxs.
2nd. Plug at 815' w/100 sxs.
3rd. Plug at 255' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

10

Signed Bruce D. Basye
(TECHNICIAN)

RECEIVED

JUL 27 2005

KCC WICHITA

INVOICED

DATE 7.27.05
2006060148

Form CP-2/3

JUL 22 2005