

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23144-00-00
Spot: SENESE Sec/Twnshp/Rge: 26-18S-24W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: FRITZLER Well #: 5-26
County: NESS Total Vertical Depth: 4330 feet

Operator License No.: 6455
Op Name: APACHE DRILLING CO, INC
Address: P.O. BOX 68
COALDAL, CO 81222

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4330	0	
SURF	8.625	231		

#140 73

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2005 9:45 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: CLINT BASE Company: APACHE DRILLING Phone: (719) 942-3137

Proposed Plugging Method: RUN TUBING TO 3969' & PUMP 45 SX CMT & 300# HULLS. PLUG AT 1500' WITH 145 SX CMT. CIRCULATE CMT TO SURFACE. TOP OFF WITH 45 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2005 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

2 TUBING ANCHORS IN HOLE, TOP ONE IS AT 4059'. PUMP 300 SX CMT DOWN BACKSIDE. RUN TEMPERATURE LOG. CMT FROM 200' TO 1800'. RUN TUBING TO 3969' & PUMP 45 SX CMT & 300# HULLS. 1ST PLUG PULLED TUBING TO 1500' & PUMPED 145 SX CMT. CIRCULATED TO SURFACE. 2ND PLUG PULLED TUBING & TOPPED OFF WITH 45 SX CMT. STAYED FULL. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4280	4282		


INVOICED

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES.

Plugged through: TBG

DATE 7.29.05
BY 2006060186

District: 01



Signed Michael Maier
(TECHNICIAN)

RECEIVED
JUL 29 2005
KCC WICHITA

Form CP-127