

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-30014-00-00  
Spot: SESW Sec/Twnshp/Rge: 33-29S-6W  
650 feet from S Section Line, 3381 feet from E Section Line  
Lease Name: CARL BELL Well #: 7  
County: KINGMAN Total Vertical Depth: 3782 feet

Operator License No.: 5920  
Op Name: BANDY, TERRY P. D/B/A TE-PE OIL &  
Address: PO BOX 522  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3388	2640	120 SX CMT
SURF	8.625	250		225 SX CMT

92  
#122

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/23/2005 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: TERRY P BANDY Company: TE-PE OIL & GAS Phone: (620) 628-4428

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/23/2005 5:00 PM KCC Agent: DONALD HOBEBRECHT

Actual Plugging Report:

Sanded 50' above perforations with 5 sacks of cement on top of sand. Shot and pulled casing to 1025' and spotted 35 sacks of cement. Pulled to 625' and spotted 35 sacks of cement. Pulled to 300' and circulated cement to surface with 75 sacks of cement.

Allied #20695

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3260	3262		

**RECEIVED  
KCC DISTRICT #2  
JUL 29 2005  
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

**INVOICED**  
DATE 8-10-05  
NO. 2006060288

RECEIVED  
AUG 10 2005  
KCC WICHITA