

3 022764

15-207-19537-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019-006
SW,NE,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.
4066 feet from south section line
791 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: STATE OF KANSAS Fee Fund
Name & FEE FUND PLUGGING
Address _____
AB oil well Gas Well _____ SWD Well/ Input Well _____

Lease/Well# BENNETT A NO.6
County ALLEN
Well Total Depth 750' feet
Production Pipe: _____ Size Feet _____
Surface Casing: 12 Size Feet 25'
D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W OIL WELL SERVICE, INC. Lic. # 3097
Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: _____ Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WAS A WELL NOT VISIBLE AT SURFACE. THE PLUGGING PROPOSAL WAS TO INSTALL SURFACE CASING, TO DRILL OUT AS MUCH OF THE WELL AS POSSIBLE, AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

RECEIVED
JUL 25 2005
KCC WICHITA

Plugging Proposal Received by: CLAYTON P. TITEL
TECHNICIAN
Plugging attended by Agent: All Part _____ None _____

Operations Completed: Hour: 11:00A.M. Day: _____ Month: 11 2005

Actual Plugging Report: 20' OF 12" SURFACE CASING WAS INSTALLED IN THE WELL.

WOOD AND CUTTINGS WERE DRILLED FROM THE WELL TO 425'. 1" PIPE WAS RAN INTO THE WELL TO 425'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 247 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.6) (THIS WELL WAS NOT NUMBERED ON THE LEASE MAP)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

Bm