

15-207-20603-00-00

3 022761

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019-036
SE,NE,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.
4126 feet from south section line
278 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Fund

Lease/Well# BENNETT A NO.7
County ALLEN
Well Total Depth 750' feet

Name & FEE FUND PLUGGING
Address _____

Production Pipe: _____ Size Feet _____
Surface Casing: 12 Size Feet 20'

AB oil well Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W OIL WELL SERVICE, INC. Lic. # 3097

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: _____ 8 Month: 7 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WAS A WELL NOT VISIBLE AT SURFACE. THE PLUGGING PROPOSAL

WAS TO INSTALL SURFACE CASING, TO DRILL OUT AS MUCH OF THE WELL AS POSSIBLE

AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

RECEIVED
JUL 25 2005

KCC WICHITA

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part _____
TECHNICIAN
None _____

Operations Completed: Hour: 11:00A.M. Day: _____ 8 Month: 7 2005

Actual Plugging Report: 20' OF 12" SURFACE CASING WAS INSTALLED IN THE WELL.

WOOD AND CUTTINGS WERE DRILLED FROM THE WELL TO 525'. 1" PIPE WAS RAN INTO

THE WELL TO 525'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED

FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 285 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.7) (THIS WELL WAS NOT NUMBERED ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

Bu