

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25423-00-00
Spot: NENWSE Sec/Twnshp/Rge: 2-12S-18W
2400 feet from S Section Line, 1575 feet from E Section Line
Lease Name: PATRICK WALTERS Well #: 1
County: ELLIS Total Vertical Depth: 3645 feet

Operator License No.: 32639
Op Name: CORAL PRODUCTION CORPORATION
Address: 1600 STOUT STREET, SUITE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	227		

118⁴⁶

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/17/2005 2:45 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LARRY PICKNER Company: MURFIN DRILLING CO., INC. Phone: (303) 623-3573

Proposed Plugging Method: Ordered out 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: JAY PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 07/17/2005 7:15 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

1st. Plug at 3630' w/25 sxs.
2nd. Plug at 1385' w/25 sxs.
3rd. Plug at 760' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

RECEIVED

JUL 28 2005

KCC WICHITA

INVOICED

DATE 7-29-05
2006060183

Form CP-2/3

JUL 22 2005