

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02193-00-00
Spot: SWNW Sec/Twnshp/Rge: 20-19S-9W
3397 feet from S Section Line, 4779 feet from E Section Line
Lease Name: ROLFS Well #: 1
County: RICE Total Vertical Depth: 3242 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 225 MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3229		150 SX CMT
SURF	8.625	235		125 SX CMT

#10537

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2005 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (785) 483-3404

Proposed Plugging Method: Sand to 2845' and cap with 5 sxs cement. Perforate at 1200', 800', and 285'. Pump 35 sxs at 1200' and 35 sxs at 800'. Circulate cement from 285' to surface.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 07/20/2005 2:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded bottom plug to 2845' and capped with 5 sacks of cement. Perforated pipe at 1200', 800', and 285'. Pumped 35 sacks of cement at 1200' and 35 sacks of cement at 800'. Pulled tubing to 285' and circulated to surface with 100 sacks of cement. Pulled tubing and topped off with 20 sacks of cement.

Allied #17996

190 sacks of 60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
2976	2996		
2899	3167		

RECEIVED
KCC DISTRICT #2
JUL 26 2005
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Greg Eves

(TECHNICIAN)

RECEIVED
AUG 10 2005
KCC WICHITA

INVOICED
DATE 8-10-05
INV. NO. 2006060298