

19733-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-121-~~00432~~
SENENE Sec/Twp/Rge 27-17S-22E
4418 feet from south section line
463 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: STATE OF KANSAS Fee Fund
Name & FEE FUND PLUGGING
Address _____
AB oil well _____ Gas Well _____ SWD Well/ Input Well _____

Lease/Well# BER07 (GPS #) W-5
County MIAMI
Well Total Depth 340 EST feet
Production Pipe: 2 Size Feet 340 EST
Surface Casing: NA Size Feet NA
E 3132 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD ROAD CHANUTE, KS. 66720

Company to plug at: Hour: _____ Day: _____ 8 Month: JUNE 2005

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERVICE Phone: 620-431-8945

Were: FILL WELL FROM TD TO SURFACE WITH PORTLAND CEMENT

Plugging Proposal Received by: FRANK GUILFOYLE

Plugging attended by Agent: All _____ Part X TECHNICIAN
None _____

Operations Completed: Hour: _____ Day: _____ 20 Month: JUNE 2005

Actual Plugging Report: PULL 3/4" PIPE AND PACKER LOOSE. PULL RUBBER OFF. DIG UP
AROUND WELL, NO SURFACE CASING. PUT IN SURFACE. WASH 3/4" DOWN INSIDE 2". WASH 1"
DOWN OUTSIDE OF 2" TO 275 FT. PUMP PORTLAND CEMENT TO SURFACE INSIDE 2" AND
OUTSIDE 2". PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 125 SACKS OF CEMENT. WELL
PLUGGED.

Remarks: CONTROL NUMBER 20050027026 GPS NUMBER BER07 Legacy Day W5
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: FRANK GUILFOYLE
TECHNICIAN

RECEIVED
JUL 18 2005
KCC WICHITA