

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-02057-00-00
Spot: NWNE Sec/Twnshp/Rge: 3-18S-1W
5146 feet from S Section Line, 1230 feet from E Section Line
Lease Name: STUCKY-HOLLOWAY Well #: 6
County: MCPHERSON Total Vertical Depth: 2973 feet

Operator License No.: 31448
Op Name: EVERHART, LAWRENCE D. DBA E & E
Address: PO BOX 451
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2776		75 SX CMT
SURF	8.625	202		135 SX CMT

#96 62

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/19/2005 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: Sand to 2700' and cap with 5 sacks of cement. Set bridge at 300'. Bail fluids to 300' and dump slurry mix to fill from 300' to surface.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 07/19/2005 12:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 2700' and capped with 5 sacks of cement. Pulled 2320' of casing. Set bridge at 300'. Bailed fluids to 300' and dumped 6 yds of slurry mix to bring to surface.

6 yds = 150 sxs cement

Smokey Valley #011391

150 sacks of 60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
2720	2732		

RECEIVED
KCC DISTRICT #2
JUL 26 2005
WICHITA, KS

Remarks: PLUGGED THROUGH SURFACE PIPE

Plugged through: CSG

District: 02

Signed Meg Eves
(TECHNICIAN)

INVOICED
DATE 8-10-05
2006060290

RECEIVED
AUG 10 2005
KCC WICHITA