

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-21075-00-00
Spot: NWNESE Sec/Twnshp/Rge: 20-20S-1W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: LELAND BOESKER Well #: 1
County: MCPHERSON Total Vertical Depth: 3047 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S. MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3047		75 SX CMT
SURF	8.625	207		130 SX CMT

#9903

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/07/2005 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed
Plugging
Method:

Sand bottom to 2919' and set 4 sacks on top of sand. Pull pipe to 430' and circulate to surface.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 01/07/2005 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

1/7/2005 -- Sanded bottom to 2919' and capped with 4 sacks of cement. Cut pipe at 1230' and pulled pipe to 430'. Pumped 150 sacks of cement and 250 lbs of cotton hulls. Stopped pumping due to loss of circulation. Tagged plug at 175'.
7/21/2005 -- Pumped 110 sacks of cement to circulate to surface.
Copeland #24948 -- 150 sxs 60/40 posmix with 4% gel
Copeland #25323 -- 110 sxs 60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3005	3009		
2970	2994		

**RECEIVED
KCC DISTRICT #2
AUG - 2 2005
WICHITA, KS**

Remarks:

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)

INVOICED
DATE 8-10-05
INV. NO. 2006060293

RECEIVED
AUG 10 2005
KCC WICHITA