

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00798-00-01
Spot: SWSESE Sec/Twnshp/Rge: 33-30S-8W
372 feet from S Section Line, 1097 feet from E Section Line
Lease Name: BANTA C Well #: 1
County: KINGMAN Total Vertical Depth: 4401 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: PO BOX 2758 221 N MAIN STE 300
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4401		150 SX CMT
SURF	8.625	160		150 SX CMT

#143⁰³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2005 8:00 AM
Plug Co. License No.: 5144 Plug Co. Name: MULL DRILLING COMPANY, INC.
Proposal Revd. from: TIM HOSS Company: MULL DRILLING COMPANY, INC. Phone: (620) 594-2403

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ WitnessType: PARTIAL
Date/Time Plugging Completed: 07/21/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded 50' above perforations with 5 sacks of cement on top of sand. Shot casing at 3020' and pulled casing to 1250' and spotted 35 sacks of cement. Pulled to 900' and spotted 35 sacks of cement. Pulled to 250' and circulated cement to surface with 80 sacks of cement.

Allied #20806

60/40 posmix with 4% gel & 2 sxs hulls

Perfs:

Top	Bot	Thru	Comments
4385	4399		
RECEIVED KCC DISTRICT #2 JUL 29 2005 WICHITA, KS			

Remarks:

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED
DATE 8-10-05
INV. NO 2006060295

RECEIVED
AUG 10 2005
KCC WICHITA