

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23072-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 5-10S-21W
2290 feet from N Section Line, 410 feet from W Section Line
Lease Name: MILLER Well #: 1
County: GRAHAM Total Vertical Depth: 3910 feet

Operator License No.: 32016
Op Name: WELLS. RODGER D. DBA PIONEER RES
Address: 177 W. LINSTONE RD.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	228		

#127⁰⁸

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/07/2005 9:30 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: DUSTY ROADS Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE
Date/Time Plugging Completed: 08/07/2005 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:


1st. Plug at 3897' w/25 sxs.
2nd. Plug at 1813' w/25 sxs.
3rd. Plug at 1003' w/100 sxs.
4th. Plug at 278' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____



(TECHNICIAN)

INVOICED

RECEIVED

DATE

8-12-05

AUG 12 2005

INV. NO

2006060309

KCC WICHITA

AUG 09 2005