

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-25250-00-00

Spot: NESWSW

Sec/Twnshp/Rge: 25-26S-16E

1211 feet from S Section Line, 4185 feet from E Section Line

Lease Name: LORANCE

Well #: B 3

County: WOODSON

Total Vertical Depth: 915 feet

Operator License No.: 31788

Op Name: VEENKER RESOURCES, INC.

Address: PO BOX 14339

OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	915		
SURF	6.625	40		

#35<sup>00</sup>

Well Type: EOR

UIC Docket No: E24328, 3

Date/Time to Plug: 07/28/2005 3:00 PM

Plug Co. License No.: 31440

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC

Proposal Rcvd. from: RANDY TRIMBLE

Company: VEENKER RESOURCES, INC.

Phone: (620) 364-5644

Proposed  
Plugging  
Method:

THIS WELL CONSISTED OF 2 7/8" CASING TO 915' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP.  
THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/28/2005 4:00 PM

KCC Agent: CLAYTON TITEL

**Actual Plugging Report:**

**Perfs:**

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE ADDED TO THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 1200 P.S.I.. 28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED  
KCC DISTRICT #3

AUG 3 2005 CPT

CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed

Clayton P. Titel  
(TECHNICIAN)

RECEIVED  
AUG 08 2005  
KCC WICHITA

INVOICED

DATE

8-11-05

INV. NO.

2005060301