

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-25388-00-00

Spot: NESWSW

Sec/Twnshp/Rge: 25-26S-16E

1247 feet from S Section Line, 4485 feet from E Section Line

Lease Name: LORANCE

Well #: B 4

County: WOODSON

Total Vertical Depth: 922 feet

Operator License No.: 31788

Op Name: VEENKER RESOURCES, INC.

Address: PO BOX 14339

OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	2.875	922		
------	-------	-----	--	--

SURF	6.625	40		
------	-------	----	--	--

#35⁰⁰

Well Type: Oil

UIC Docket No:

Date/Time to Plug: 07/28/2005 1:30 PM

Plug Co. License No.: 31440

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC

Proposal Rcvd. from: RANDY TRIMBLE

Company: VEENKER RESOURCES, INC.

Phone: (620) 364-5644

Proposed
Plugging
Method:

THIS WELL CONSISTED OF 2 7/8" CASING TO 922' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP.
THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: NONE

Date/Time Plugging Completed: 07/28/2005 2:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE ADDED TO THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 500 P.S.I.. 25 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3

AUG 3 2005 CPT

CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed

Clayton R. Titel

(TECHNICIAN)

RECEIVED

AUG 08 2005

KCC WICHITA

INVOICED

DATE 8-11-05
2005060301

Form CP-2/3