

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-25006-00-00

Spot: SENWSW

Sec/Twnshp/Rge: 25-26S-16E

1447 feet from S Section Line, 4172 feet from E Section Line

Lease Name: LORANCE

Well #: 1

County: WOODSON

Total Vertical Depth: 957 feet

Operator License No.: 31788

Op Name: VEENKER RESOURCES, INC.

Address: PO BOX 14339

OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	958		
SURF	6.625	40		

\$ 35.00

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/28/2005 2:30 PM

Plug Co. License No.: 31440

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC

Proposal Rcvd. from: RANDY TRIMBLE

Company: VEENKER RESOURCES, INC.

Phone: (620) 364-5644

Proposed
Plugging
Method:

THIS WELL CONSISTED OF 2 7/8" CASING TO 957.7' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/28/2005 3:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTONSEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE MIXED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 800 PSI. 23 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3

AUG 3 2005 CPT

CHANUTE, KS

Remarks: LOCATION STATED ABOVE IS FROM GPS SURVEY.

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED

AUG 08 2005

KCC WICHITA

INVOICE

DATE

8-11-05

WELL NO

2006060301