

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25435-00-00
Spot: SWSE Sec/Twnshp/Rge: 3-15S-18W
700 feet from S Section Line, 2020 feet from E Section Line
Lease Name: PFEIFER WASINGER Well #: 1
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	210	0	

120²⁵

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/04/2005 10:00 PM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: DARREL ANDERSON Company: ANDERSON, C. D. DBA ANDERSON Phone: (785) 421-2234

Proposed Plugging Method: Ordered 165 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 08/04/2005 11:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report: _____ Perfs: _____

1st. Plug at 3650' w/25 sxs.
2nd. Plug at 1230' w/25 sxs.
3rd. Plug at 550' w/50 sxs.
4th. Plug at 260' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce D. Basye

RECEIVED

AUG 12 2005

KCC WICHITA

Form CP-2/3

INVOICED

DATE 8-12-05

INV. NO. 2006060302

AUG 09 2005