

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03203-00-01
Spot: W2SWSW Sec/Twnshp/Rge: 5-9S-17W
720 feet from S Section Line, 330 feet from W Section Line
Lease Name: THOMPSON Well #: 1
County: ROOKS Total Vertical Depth: 690 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	236	0	

35⁰⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/09/2005 10:00 AM
Plug Co. License No.: 8925 Plug Co. Name: LIBERTY OPER & COMPL, INC
Proposal Rcvd. from: CHARLIE FARR Company: LIBERTY OPER & COMPL, INC Phone: (785) 434-4686

Proposed Plugging Method: 1. Ordered out 100 sxs 60/40 pozmix - 10% gel with 500# hulls.
2. Ordered out 100 sxs 60/40 pozmix - 10% gel.
Unable to wash down - well below 690' - lost hole.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/09/2005 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 600'. Allied pumped 100 sxs 60/40 pozmix - 10% gel with 500# hulls.
Did not circulate cement. PTOH. W.O.C three hours.
Ran tubing back in hole to 600'. Allied pumped 70 sxs cement with 500# hulls - circulated cement.
PTOH cement 8' down.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

8-12-05

INV. NO

2006060305

RECEIVED

AUG 12 2005

KCC WICHITA

Form CP-2/3

AUG 10 2005